



Normal Checklists

Chapter NC

PREFLIGHT

Oxygen Tested, 100%

NAVIGATION transfer
and DISPLAY switches NORMAL, AUTO

Window heat ON

Flight instruments Heading ____, Altimeter ____

Parking brake Set

Engine start levers CUTOFF

BEFORE START

Flight deck door Closed and locked

Fuel ____ KGS, PUMPS ON

Passenger signs ____

Windows Locked

MCP V2____, HDG____, ALT____

Takeoff speeds V1____, VR____, V2____

CDU preflight Completed

Trim ____ UNITS, 0, 0

Taxi and takeoff briefing Completed

ANTI COLLISION light ON



BEFORE TAXI

Generators ON
Probe heat ON
Anti-ice ____
Isolation valve AUTO
ENGINE START switches CONT
Recall Checked
Autobrake RTO
Engine start levers IDLE detent
Flight controls Checked
Ground equipment Clear

BEFORE TAKEOFF

Flaps ____, green light

AFTER TAKEOFF

Engine bleeds ON
Packs AUTO
Landing gear UP and OFF
Flaps UP, no lights

DESCENT

Recall Checked
Autobrake ____
Landing data VREF ____, Minimums ____
Approach briefing Completed



737 Flight Crew Operations Manual

APPROACH

Altimeters

LANDING

ENGINE START switches CONT

Speedbrake ARMED

Landing gear Down

Flaps , green light

SHUTDOWN

Fuel pumps OFF

Probe heat OFF

Hydraulic panel Set

Flaps UP

Parking brake

Engine start levers CUTOFF

Weather radar OFF

SECURE

IRSs OFF

Emergency exit lights OFF

WINDOW HEAT OFF

Packs OFF